

Item No.	Description	Qty	Unit	Material Cost	Equipment Cost	Labor Cost	Estimated Direct Cost	Mark-ups in Percent		Total Mark Up Value 10	VAT 11	Total Indirect Cost 12	Total Cost 13	Unit Cost 14
								OCM	Profit					
	2500kVA Distribution Transformer, 13.80kV / 0.460kV Delta-Wye Grounded, Oil Immersed with Enclosure for Bushing Terminals (ABB Brand or Equivalent Brand)	1.00	unit											
	Consumables	1.00	lot											
EE5	FROM DISTRIBUTION TRANSFORMER TO LVSG-MAIN & ATS-1/LVSG-1&2	1.00	lot				-	-	-	-	-	-	-	-
	LVSG-1/ ATS-1/MDP1 (Main: 1-4000A,3P,600V,100kAIC, ACB; Branches: 2 - 1600A, 2-400A & 1-300A MCCB)	1.00	set											
	LVSG-2/ATS-1/MDP2 (Main: 1-4000A,3P,600V,100kAIC, ACB; Branches: 1 - 2500A, 2-400A, 1-250A, 1-200A & 1-125A MCCB)	1.00	unit											
	Tie-Breaker w/ Electrical and Mechanical Interlocked @3200A,3P,ACB	1.00	set											
	250mm2 THW Copper wire	1.098	m											
	100mm2 THW Copper wire	600.00	m											
	G.I.Fabricated Cable Tray w/ Hanger and support (0.60m width x 20LM)	20.00	Lin											
	Terminal Eye, Long type (250mm2)	120.00	pcs											
	Terminal Eye, Long type (100mm2)	40.00	pcs											
	Boxes and Splicing Box	1.00	lot											
	Consumables	1.00	lot											
EE6	ELECTRICAL GROUNDING SYSTEM	1.00	lot				-	-	-	-	-	-	-	-
	100mm2 Bare Copper Wire	300.00	m											
	Grounding Rod (3/4in x 10ft)	8.00	pcs											
	Grounding Pit w/ cover	8.00	sets											
	Exothermic Bonding Material	1.00	lot											
	Grounding Connector (3/4in dia)	42.00	pcs											
	Terminal Eye (100mm2)	8.00	pcs											
	Consumables	1.00	lot											
4.0	MECHANICAL WORKS			-	-	-	-	-	-	-	-	-	-	-
ME1	FIRE PROTECTION SYSTEM	15.00	Tanks				-	-	-	-	-	-	-	-
	HFC-226fa Ceiling Mounted 20LBS	13.00	Tanks											
	HFC-226fa Wheel Type 50LBS	2.00	Tanks											
	Hangers & Support	1.00	lot											
5.0	AUXILIARY WORKS			-	-	-	-	-	-	-	-	-	-	-
AU1	CLOSE CIRCUIT TELEVISION SYSTEM	13.00	units				-	-	-	-	-	-	-	-
	IP Camera (Dome Type) 3MP	7.00	units											
	IP Camera (Bullet Type) 3MP	6.00	units											
	Network video recorder (NVR) 16 Channel High Definition Advance	1.00	set											
	Gigabit Port Switch 16 Ports	1.00	pc											
	Gigabit Port Hub 16 Ports	1.00	pc											
	Hard Drive / HDD 6TB	2.00	pcs											
	Monitor/Led TV 32 Inch	1.00	pc											
	HDMI Cables	1.00	pc											
	UTP Cables and other Network Cables (Cat 6)	5.00	box											
	Uninterrupted Power Supply (UPS)	1.00	pc											
	Pipings, Connection Hangers and Supports	1.00	lot											
	Catenaries, Links, couplings, bolts and others	1.00	lot											
	Other consumables Materials and accessories	1.00	lot											
AU2	CCTV ROUGH INS	1.00	LOT											
AU3	FIRE DETECTION AND ALARM SYSTEM (FDAS)	1.00	lot											
	Addressable Fire alarm Sirens FDAS Control Panel 4 zone 24 VDC	1.00	pc											
	Smoke detector	3.00	pc											
	Heat detector	6.00	pc											
	Digital Manual call point	3.00	pc											
	Fire Alarm Sirens with Stroke Light	3.00	pc											
	Stroke light indicator	1.00	pc											
	TF Wire (Color Coding)	4.00	pc											
	Voltage regulator 500VA	1.00	pc											
	UPS Power Backup 1000VA	1.00	pc											
	Batteries 7AH	1.00	pc											
	Smoke tester 150ml	1.00	pc											
	Pipings, Connection Hangers and Supports, Catenaries, Links, couplings, bolts and others	1.00	lot											
	Others (Batteries 7A, 12 VDC)	1.00	pc											
AU4	FDAS ROUGH INS	1.00	LOT											
	Grand Total Cost			-	-	-	-	-	-	-	-	-	-	-

PREPARED BY:

Item No.	Description	Qty	Unit	Material Cost	Equipment Cost	Labor Cost	Estimated Direct Cost	Mark-ups in Percent		Total Mark Up Value	VAT	Total Indirect Cost	Total Cost	Unit Cost
								OCM	Profit					
	<i>TF Wire (Color Coding)</i>	4.00	pc											
	<i>Voltage regulator 500VA</i>	1.00	pc											
	<i>UPS Power Backup 1000VA</i>	1.00	pc											
	<i>Battery 7AH</i>	1.00	pc											
	<i>Smoke tester 15mm</i>	1.00	pc											
	<i>Pipings, Connection Hangers and Supports, Cateneraries, Links, couplings, bolts and others</i>	1.00	lot											
	<i>Others (Battery 7A, 12-VDC)</i>	1.00	pc											
AL4	FDAS ROUGH INS	1.00	LOT											
	Grand Total Cost			-	-	-	-	-	-	-	-	-	-	-

PREPARED BY: